S.N	DESCRIPTION OF WORK	N	L	B	D	QTY	UNIT	RATE	AMOUNT
6	Providing **TMT Steel Reinforcement for R.C.C work** including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.**TMT Bars Fe 500**								
	S.R.page 19 item 4.46.2								
a	For column					1.40	cumt		
	2.0%					0.03			
	7850 kg/cmt					219.39	kgs		
						0.22	MT	**69456.50**	**15238.19**
	Basic Rate:	64635.00							
	Add: Lift Charges for First Floor	445.00							
	Add: Lift Charges for Terrace Floor	445.00							
	Total for First Floor	65525.00							
	Area Weightage @ 6%	3931.50							
	Total	69456.50							
7	Providing and fixing 1mm thick **M.S. sheet garage door** with frame and diagonal braces of size 40x40x6 mm angle Iron, 3.15mm thick M.S. Gusset plates at the junctions and corners, with handles, stoppers and locking arrangements etc., including applying a priming coat of red lead paint cost of materials, labour, HOM of machinery complete as per specifications. Double leaf door of size 2.4x2.4m								
	S.R.page 31 item 7.3								
	D	1	1.00	2.10		2.10			
						2.10	Sqmt	**2660.60**	**5587.26**
	Basic Rate:	2500.00							
	Add: Lift Charges for First Floor	5.00							
	Add: Lift Charges for Terrace Floor	5.00							
	Total	2510.00							
	Area Weightage @ 6%	150.60							
	Total	2660.60							
8	: Providing and fixing 1mm thick **M.S. sheet sliding shutters** with frame and diagonal braces of 40x40x6 mm angle Iron 3.15mm thick M.S. Gusset plates at junctions and corners, 25mm dia pulley, 40x40x6 mm angles and T iron guide rail top and bottom respectively with handles, stoppers and locking arrangements etc., including applying a priming coat of red lead paint cost of materials, labour, HOM of machinery complete as per specifications.								
	S.R.page 31 item 7.2								
	D	1	1.00	2.10		2.10			
						2.10	Sqmt	**3286.00**	**6900.60**
	Basic Rate:	3090.00							
	Add: Lift Charges for First Floor	5.00							
	Add: Lift Charges for Terrace Floor	5.00							
	Total	3100.00							
	Area Weightage @ 6%	186.00							
	Total	3286.00							
9	Providing and applying painting in two coats with plastic Emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications and as per the directions of the Engineer in charge. (with Primer)								
	S.R.page 113 item15.51.2								
	Internal Walls					40.62			
						40.62	Sqmt	**90.10**	**3659.86**
	Basic Rate:	85.00							
	Area Weightage @ 6%	5.10							
	Total	90.10							

S.N	DESCRIPTION OF WORK	N	L	B	D	QTY	UNIT	RATE	AMOUNT
10	Providing and finishing external walls in two coats over one coat of 100% acrylic silicon glazed primer with antifungal paint for top coat of approved brand and shade to give an even shade after thoroughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications.								
	S.R.page124 Item 15.104								
	External walls					216.36			
						216.36	Sqmt	**162.18**	**35089.33**
	Basic Rate:	147.00							
	Addt: Scaffolding Charges for First Floor	3.00							
	Addt: Scaffolding Charges for TerraceFloor	3.00							
	Total	153.00							
	Area Weightage @ 6%	9.18							
	Total	162.18							
11	Providing and applying painting two coats (excluding priming coat) on new wood surface and / or wood basedsurface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost ofmaterials, labour, complete as per specifications.								
	S.R.page 118 item 15.60.1								
	D	1	1.00	2.10		2.10			
						2.10			
			2.10	2.25		**4.73**	Sqmt	**85.86**	**405.69**
	Basic Rate	81.00							
	Area Weightage 6%	4.86							
	Total	85.86							
12	Providing and laying to required line and slope roofing with **corrugated asbestos cement sheet 6mm**. thick fixed with galvanised iron J or L hooks, bolts and nuts 8mm. dia C.I plain and bitumen washers over the existing purlins, rafters and trusses including cost of materials, labour, complete as per specifications.								
	S.R.page 46 item 8.3								
		1	3.80	6.50		24.70			
						24.70	Sqmt	**373.12**	**9216.06**
	Basic Rate	352.00							
	Area Weightage 6%	21.12							
	Total	373.12							
13	Providing and laying integral cement based waterproofing treatment including preparation of surface as required for treatment of roofs, balconies, terraces etc., consisting of following application. (a) Applying and grouting a slurry coat of neat cement using 2.75 kg/sqm of cement admixed with proprietary water proofing compound conforming to IS:2645 over the RCC slab after cleaning the surface before treatment. (b) Laying cement concrete using broken brick bats 25mm to 100mm size with 50% of cement mortar 1:5 admixed with proprietary water proofing compound conforming IS:2645 over 20mm thick layer of cement mortar 1:5 admixed with proprietary water proofing compound to required slope and treating similarly the adjoining walls upto 300mm height including rounding off junctions of walls andslabs. (c) After two days of proper curing, applying a second coat of cement lurry admixed with proprietary water proofing compound (d) Finishing the surface with 20mm thick jointless cement mortar of mix 1:4 admixed with proprietary water proofing compound and finally finishing the surface with trowel and neat cement slurry and making of 300x300mm square. (e) The whole terrace so finished shall be flooded with water for a minimum period of two weeks for curing and for final test including cost of materials, labour complete as per specifications.								
	S.R.page 66 item 10.2								
		1	9.63	15.60		150.23			
		1	7.95	8.20		65.19			
		1	9.65	3.82		36.86			
						252.28	Sqmt	**909.48**	**229444.52**
	Basic Rate:	858.00							
	Area Weightage @ 6%	51.48							
	Total	909.48							